

Cement Test Certificate Final

801 Berrimah Road, East Arm NT 0828 PO Box 39631, Winnellie NT 0821 T: +61 8 8984 0600 F: +61 8 8984 0610

www.adbri.com.au

ABN 22 009 593 515

Type GP General Purpose Cement

Test Certificate Number: 170393

Product Certified:

Produced At: Northern Cement, Darwin Plant, NT

 Sample Code:
 B05c600

 Sample Date:
 21/07/2017

| Nominal Blend | Requirements | Result |
|---|--------------|---------|
| Clinker | | >86.5 % |
| Ground Granulated Iron Blast-Furnace Slag | | Nil |
| Mineral Addition | Max 7.5 % | <7.5 % |
| Calcium Sulphate | | <5 % |
| Minor Additional Constituents | Max 5 % | Nil |

| Reportable Property | Test Method | Requirements of | Result |
|---|-------------|-----------------|-----------|
| | | AS3972 | |
| 3 Day Strength | AS2350.11 | N/R | 36.3 MPa |
| 7 Day Strength | AS2350.11 | Min 35.0 MPa | 48.4 MPa |
| 28 Day Strength | AS2350.11 | Min 45.0 MPa | 60.1 MPa |
| Initial Set Time | AS2350.4 | Min 45 min | 90 min |
| Final Set Time | AS2350.4 | Max 360 min | 180 min |
| Soundness | AS2350.5 | Max 5 mm | 1 mm |
| Sulfuric Anhydride content (SO ₃) | AS2350.2 | Max 3.5 % | 2.8 % |
| Chloride Ion | BH-TM-0507 | Max 0.10 % | 0.017 % |
| Other Properties | | | |
| SiO ₂ | AS2350.2 | N/R | 19.6 % |
| Al_2O_3 | AS2350.2 | N/R | 5.4 % |
| Fe_2O_3 | AS2350.2 | N/R | 2.8 % |
| CaO | AS2350.2 | N/R | 64.2 % |
| MgO | AS2350.2 | N/R | 1.2 % |
| Na₂O Equivalent | AS2350.2 | N/R | 0.6 % |
| Loss on Ignition | AS2350.2 | N/R | 2.2 % |
| Fineness Index | AS2350.8 | N/R | 355 m²/kg |
| Normal Consistency | AS2350.3 | N/R | 28.8 % |

This document shall not be reproduced except in full.

REMARKS

These test results apply specifically to the above designated sample as received for the date shown.

Adelaide Brighton Cement Birkenhead Laboratory (Accredited number: 252), 62 Elder Rd Birkenhead 5015, is responsible for testing in accordance with AS2350.2:2006, AS2350.8:2006 and in-house method BH-TM-0507.

Adelaide Brighton Cement Angaston Laboratory (Accredited number: 73), Stockwell Rd Angaston 5353, is responsible for testing in accordance with AS2350.3:2006, AS2350.4:2006, AS2350.5:2006, AS2350.11:2006 and AS2350.12:2006.

This despatch grab sample complies to the requirements of AS3972:2010, Type GP Cement.

N/R = No Requirement



Accredited for compliance with ISO/IEC 17025 - Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Approved Signatory

F. Pope

Issue Date: 5/09/2017