

**Product Certified:** Type GP General Purpose Cement  
**Test Certificate Number:** 190433  
**Produced At:** Northern Cement, Darwin Plant, NT  
**Sample Code:** B06fc81  
**Sample Date:** 8/08/2019

| Nominal Blend                             | Requirements | Result  |
|---|--------------|---------|
| Clinker                                   |              | >86.5 % |
| Ground Granulated Iron Blast-Furnace Slag |              | Nil     |
| Mineral Addition                          | Max 7.5 %    | <7.5 %  |
| Calcium Sulphate                          |              | <5 %    |
| Minor Additional Constituents             | Max 5 %      | Nil     |

| Reportable Property                           | Test Method | Requirements of AS3972 | Result   |
|---|-------------|------------------------|----------|
| 3 Day Strength                                | AS2350.11   | N/R                    | 37.7 MPa |
| 7 Day Strength                                | AS2350.11   | Min 35.0 MPa           | 51.6 MPa |
| 28 Day Strength                               | AS2350.11   | Min 45.0 MPa           | 63.8 MPa |
| Initial Set Time                              | AS2350.4    | Min 45 min             | 135 min  |
| Final Set Time                                | AS2350.4    | Max 360 min            | 195 min  |
| Soundness                                     | AS2350.5    | Max 5 mm               | 1 mm     |
| Sulfuric Anhydride content (SO <sub>3</sub> ) | AS2350.2    | Max 3.5 %              | 3.1 %    |
| Chloride Ion                                  | BH-TM-0507  | Max 0.10 %             | 0.012 %  |

**Other Properties**

|                                |          |     |                        |
|--------------------------------|----------|-----|------------------------|
| SiO <sub>2</sub>               | AS2350.2 | N/R | 20.2 %                 |
| Al <sub>2</sub> O <sub>3</sub> | AS2350.2 | N/R | 5.6 %                  |
| Fe <sub>2</sub> O <sub>3</sub> | AS2350.2 | N/R | 2.9 %                  |
| CaO                            | AS2350.2 | N/R | 63.5 %                 |
| MgO                            | AS2350.2 | N/R | 1.6 %                  |
| Na <sub>2</sub> O Equivalent   | AS2350.2 | N/R | 0.6 %                  |
| Loss on Ignition               | AS2350.2 | N/R | 2.1 %                  |
| Fineness Index                 | AS2350.8 | N/R | 355 m <sup>2</sup> /kg |
| Normal Consistency             | AS2350.3 | N/R | 28.8 %                 |

*This document shall not be reproduced except in full.*

**REMARKS**

These test result apply specifically to the sample as received at the Adelaide Brighton Cement Birkenhead Laboratory (Accreditation number: 252), 62 Elder Rd Birkenhead SA 5015.

This despatch grab sample complies to the requirements of AS3972:2010, Type GP Cement.

N/R = No Requirement



Accredited for compliance with ISO/IEC 17025 - Testing. The results of the tests, calibrations and/or measurements included in this document are traceable to Australian/national standards.

Approved Signatory

F. Pope

**Issue Date:** 19/09/2019